

# RANDWICK CAMPUS REDEVELOPMENT

**Hospital Road Stormwater Upgrade Fact Sheet – September 2021** 

### Stormwater upgrade on Hospital Road

Stormwater infrastructure upgrades will commence shortly on Hospital Road and Magill Street. The upgrades will increase the capacity of the local stormwater system for the neighbourhood and support the stormwater requirements of the Randwick Campus Redevelopment.

The stormwater upgrade works include:

- site preparatory works and vegetation management
- saw cutting of the existing road surface
- excavation works
- installation of new stormwater pipes
- backfilling of the trench
- temporary reinstatement of the road surface.

Once completed, the road surface will be permanently reinstated.

### Scheduling works

In preparation for the stormwater upgrades, service investigations and relocations are required and will commence shortly.

The stormwater upgrade works are anticipated to occur through late 2021.

Due to current Covid-19 restrictions, dates are subject to change due to workforce availability.

See overleaf for more information about the location of the works.

### Timeline for stormwater upgrade on Hospital Road





### **Managing construction activity**

The Randwick Campus Redevelopment complies with strict environmental and planning controls. During construction we are committed to minimising disturbance to our neighbours and local community.

To maintain traffic and access and ensure operational continuity of the Randwick Hospitals Campus:

- works will be completed in sections along Hospital Road before crossing into Magill Street
- Hospital Road will be reduced to a single lane for vehicular use for the duration of the works
- traffic management will be in place to ensure the safe movement of vehicles
- installation of infrastructure across Hospital Road will be scheduled on weekends when hospital logistics demands are lower.

### Managing noise, dust and vibration

Measures to manage noise, vibration and dust will be implemented for the duration of works. These include:

- selection and use of equipment to manage construction impacts, such as using saws in place of jackhammers where possible
- respite periods for high noise activities
- staging the work to allow the compound to move as each section is completed
- wetting down of the work area to ensure appropriate dust management
- turning off equipment when not in use
- noise and vibration monitoring in place.

For more information







## RANDWICK **CAMPUS REDEVELOPMENT**

Hospital Road Stormwater Upgrade Fact Sheet – September 2021

#### Hours of work

Approved work hours are:

- 6am to 10pm Monday to Friday
- 7am to 5pm Saturdays.

Some activities during the stormwater infrastructure upgrade will require periods of out of hours work to ensure operational continuity of the Randwick Hospitals Campus is maintained.

Notification will be provided to residents in advance of any out of hours works occurring.

### Thank you for your patience while we progress these important activities

Ongoing updates via letterbox drops and phone calls will be provided to ensure affected stakeholders and residents remain informed.

We are working closely with the Randwick Hospitals Campus, Emergency Services, Transport for NSW, and Randwick City Council to coordinate construction in the Randwick Health & Innovation Precinct.

### Location of works - Hospital Road stormwater upgrade



### Sorry we didn't door knock

While we had plans to door knock and discuss these works face to face, we are following NSW Health advice and complying with Covid-19 physical distancing measures to keep the community safe.

If you would like to learn more about the project or arrange an online meeting or a phone conversation, please get in touch with the project team via phone on 1800 571 866, or email via randwickcampusredevelopment@health.nsw.gov.au

For more information



